



अखिल भारतीय आयुर्विज्ञान संस्थान , बिलासपुर  
हिमाचल प्रदेश -१७४००१  
All India Institute of Medical Sciences, Bilaspur  
Himachal Pradesh-174001  
<https://aiimsbilaspur.edu.in>  
[engineering@aiimsbilaspur.edu.in](mailto:engineering@aiimsbilaspur.edu.in)



AIIMS-BLS-H-24/EE-0003/2024-25

Dated: 24/10/2024

## **NOTICE INVITING QUOTATION**

Sealed item rate quotations as per schedule attached are hereby invited by the undersigned on behalf of the Executive Director, AIIMS Bilaspur (HP) from registered contractors so as to reach in this office on or before **04/11/2024 up to 03:00 PM** and shall be opened on the same day at **03:30 PM** in the O/o Executive Engineer, AIIMS Bilaspur (HP) in the presence of intending contractors or their authorized representatives.

**Name of work: Providing Brick work & revolving gate at open entries behind type IV & UG students Mess**

**Estimated Cost: Rs 54699/-**

-----As Per Schedule Attached-----

### **Terms & Conditions: -**

1. The work will be carried out as per CPWD General Specifications for Civil Works amended up to date & as per the instructions of the Engineer-in-charge.
2. The work is to be completed within 30 days from issue of work order.
3. Any damages done during execution of the work/repairs are to be made good by the agency and nothing extra will be paid separately for the same.
4. The Prices quoted should be inclusive of all taxes including GST and nothing extra is to be paid.
5. Agency shall abide by labour rules.
6. All the applicable taxes shall be deducted from the bill.
7. Compensation of delay work will be @0.5% per week.
8. GST Registration Certificate should also be attached with NIQ.
9. Certificate of enlistment with Central/State Govt. Organization/Central Autonomous body/Central Public Sector Undertaking should also be attached with NIQ.
10. All material to be used on the work will have to be got approved from the Engineer-in-charge.

Sd/-  
Executive Engineer

Copy To:-

- (i) Institute Website
- (ii) Notice Board

Sd/-  
Executive Engineer



Schedule Of Quantity

Providing Brick work & revolving gate at open entries behind type IV & UG students Mess

Sr. No.	Description of Item	Qty.	Unit	Rate (In ₹)	Total Amount (In ₹)
				(In Figures)	
1.	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :  Cement mortar 1:6 (1 cement : 6 coarse sand)	2.24	Cum		
2.	12 mm cement plaster of mix :  1:4 (1 cement: 4 coarse sand)	22.68	sqm		
3.	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	22.68	sqm		
4.	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound ) content.  With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre.	22.68	sqm		
5.	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound ) content less than 50 grams/ litre,	22.68	sqm		



अखिल भारतीय आयुर्विज्ञान संस्थान , बिलासपुर  
हिमाचल प्रदेश -१७४००१  
**All India Institute of Medical Sciences, Bilaspur**  
**Himachal Pradesh-174001**  
<https://aiimsbilaspur.edu.in>  
[engineering@aiimsbilaspur.edu.in](mailto:engineering@aiimsbilaspur.edu.in)



	of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour.  Two coats.				
6.	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.  Hot finished welded type tubes	52.00	kg		
7.	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :  Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	2.88	sqm		