



अखिल भारतीय आयुर्विज्ञान संस्थान , बिलासपुर
हिमाचल प्रदेश -१७४००१
All India Institute of Medical Sciences, Bilaspur
Himachal Pradesh-174001
<https://aiimsbilaspur.edu.in>
engineering@aiimsbilaspur.edu.in



AIIMS-BLS-H-24/EE-0001/2024-25

Dated: 11/06/2024

NOTICE INVITING QUOTATION

Sealed item rate quotations as per schedule attached are hereby invited by the undersigned on behalf of the Executive Director, AIIMS Bilaspur (HP) from registered contractors so as to reach in this office on or before **25/06/2024 up to 03:00 PM** and shall be opened on the same day at **03:30 PM** in the O/o Executive Engineer, AIIMS Bilaspur (HP) in the presence of intending contractors or their authorized representatives.

Name of work: Civil work in ENMG cum EP Lab (Neurology), Hospital Block, 3rd floor, at AIIMS Bilaspur”.

-----As Per Schedule Attached-----

Terms & Conditions: -

1. The work will be carried out as per CPWD General Specifications for Civil Works amended up to date & as per the instructions of the Engineer-in-charge.
2. The work is to be completed within 15 days from issue of work order.
3. Any damages done during execution of the work/repairs are to be made good by the agency and nothing extra will be paid separately for the same.
4. The Prices quoted should be inclusive of all taxes including GST and nothing extra is to be paid.
5. Agency shall abide by labour rules.
6. All the applicable taxes shall be deducted from the bill.
7. Compensation of delay work will be @0.5% per week subject of maximum of 10 %
8. GST Registration Certificate should also be attached with NIQ.
9. Certificate of enlistment with Central/State Govt. Organization/Central Autonomous body/Central Public Sector Undertaking should also be attached with NIQ.
10. All material to be used on the work will have to be got approved from the Engineer-in-charge.

Sd/-
Executive Engineer

Copy To: -

- (i) Institute Website
- (ii) Notice Board

Sd/-
Executive Engineer

Schedule of Quantity

Civil work in ENMG cum EP Lab (Neurology), Hospital Block at AIIMS Bilaspur.

S.No	Description of work	Qty	Unit	Rate	Amount
Civil					
				In Figure	In Words
1	66mm overall thickness partition using 8mm thick, double skin multipurpose cement board, Type-B, Category-III as per IS : 14862:2000 reinforced with cellulose fibre manufactured through autoclaving process (High pressure steam cured) with suitable fibre cement screws	25	SQM		
2	Distemping with 1st quality acrylic distemper (ready mixed) having VOC (Volatile Organic Compound) content less than 50 gram/ litre, of approved brand and of required shade and colour complete to give and even shade.				
	Old work (one or more coats)	50	SQM		
3	Providing and fixing brass curtain rods of wall thickness 1.25mm with two brass brackets fixed with brass screws and wooden plugs etc. wherever necessary complete.				
	20 mm diameter.	5.5	m		