



अखिल भारतीय आयुर्विज्ञान संस्थान , बिलासपुर  
हिमाचल प्रदेश -१७४००१  
**All India Institute of Medical Sciences, Bilaspur**  
**Himachal Pradesh-174001**  
<https://aiimsbilaspur.edu.in>  
[engineering@aiimsbilaspur.edu.in](mailto:engineering@aiimsbilaspur.edu.in)



AIIMS-BLS-H-24/EE-0001/2023-24

Dated: 20/02/2024

### **NOTICE INVITING QUOTATION**

Sealed item rate quotations as per schedule attached are hereby invited by the undersigned on behalf of the Executive Director, AIIMS Bilaspur (HP) from registered contractors so as to reach in this office on or before **24/02/2024 up to 03:00 PM** and shall be opened on the same day at **03:30 PM** in the O/o Executive Engineer, AIIMS Bilaspur (HP) in the presence of intending contractors or their authorized representatives.

**Name of work: Covering of MS Bridge for MGPS extension work from LMO to Ayush With ACP**

**Estimated Cost: Rs 4.43 Lakhs**

-----As Per Schedule Attached-----

#### **Terms & Conditions: -**

1. The work will be carried out as per CPWD General Specifications for Civil Works amended up to date & as per the instructions of the Engineer-in-charge.
2. The work is to be completed within 15 days from issue of work order.
3. Any damages done during execution of the work/repairs are to be made good by the agency and nothing extra will be paid separately for the same.
4. The Prices quoted should be inclusive of all taxes including GST and nothing extra is to be paid.
5. Agency shall abide by labour rules.
6. All the applicable taxes shall be deducted from the bill.
7. Compensation of delay work will be @0.5% per week.
8. GST Registration Certificate should also be attached with NIQ.
9. Certificate of enlistment with Central/State Govt. Organization/Central Autonomous body/Central Public Sector Undertaking should also be attached with NIQ.
10. All material to be used on the work will have to be got approved from the Engineer-in-charge.

Sd/-  
Executive Engineer

Copy To:-

- (i) Institute Website
- (ii) Notice Board

Sd/-  
Executive Engineer

**Schedule Of Quantity**

**Covering of MS Bridge for MGPS extension work from LMO to Ayush Block With ACP**

Sr. No.	Description of Item	Qty.	Unit	Rate (In Rs)		Amount (In Rs)
				(In Figures)	(In Words)	
1.	Providing, fabricating and supplying and fixing panels of aluminum composite panel cladding in pan shape in metallic colour of approved shades made out of 4mm thick aluminum composite panel material consisting of 3mm thick FR grade mineral core sandwiched between two aluminium sheets (each 0.5mm thick) as specified using stainless steel screws, nuts, bolts, washers, cleats, weather silicone sealant, MS brackets etc. for all heights and all levels etc.	79.67	Sqm.			